

6-440 KY 237 Multi-Use Path Project

BCFY22-26

Bid Opening: December 23, 2021

Questions & Answers #1

Q. I need to find out about the Line 2555 Concrete Class-B at 104 cubic yards; is this in reference to the Gravity Wall located starting at Station 168+0.00? If not, what is it for and is there a line item going to be added for this Gravity Wall with specification on the design build?"

A. Yes, the concrete is for the retaining wall.

Q. How do we get paid for the RCP at the headwalls?

A. All Pipe Extensions have pipe quantity included on the pipe drainage summary and is shown on the pipe sheets

Q. Need clarification on modified curb (change in depth/width, etc).

A. The width of the modified curb and gutter will be same as standard, but the depth will need to be determined in the field based on pavement thickness.

Q. Note on sheet T01 states "where affected, loop lead-in wire shall be replaced all the way to the controller". However, several plan sheets reference splicing GES loop lead-ins in junction boxes. Will there be an overrun in 14/1 pair quantities if these lead-ins are "affected" and need to be replaced in their entirety?

A. Splicing is intended to be the method used and if replaced then an overrun will be paid.

Q. Is there a detail for Handrail A1?

A. Detail is Standard Drawing RGX 030-06