

CITY OF NORTHGLENN

**CROKE RESERVOIR RAIL PAINTING
IFB 2023-019**

ADDENDUM NO. 1

DATED: August 16, 2023

TO: PROSPECTIVE BIDDERS

The following adds to, supplements, amends or clarifies by way of explanation, portions of the Contract Documents, Specifications, and Drawings for the above named project.

NOTE: It will be the responsibility of the Bidder to acknowledge receipt of Addenda on the Bid Form as part of his/her submitted proposal. Failure to do so will be grounds for the City to reject the proposal.

The Contract Documents, including the Specifications and Drawings are hereby modified by the following items:

QUESTIONS:

We have the following questions regarding the above referenced project:

Q1. No products are listed in the Special Conditions. Is there a specific brand and type of paint required for this project?

A1. *As mentioned under Surface Preparation and Paint Specifications in Volume 2 of the IFB the following types and required thicknesses of Sherwin Williams Paint are listed below:*

Metal: Miscellaneous. Iron, Ornamental Iron, Structural Iron and Steel, Ferrous Metal.

1. Alkyd Systems; Waterbased:

a. Semi-Gloss or Gloss Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W Pro Industrial Waterbased Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series (4.0-5.0 mils wet, 1.4 - 1.7 mils dry per coat).
- 3) 3rd Coat: S-W Pro Industrial Waterbased Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series (4.0-5.0 mils wet, 1.4 - 1.7 mils dry per coat).

END OF QUESTIONS

Bid Alternate Items 14, 15, 16, 17 and 18 have been added to the IFB and are shown in the revised bid summary. Item 18 Retaining Wall Stone Repair involves procuring and installing a small number of replacement cosmetic stones that match the existing. Below are photos of these additional items:



Vertical Picket Steel Fence
(Bid Alternate Items 14 & 15)



Vertical Picket Steel Fence
(Bid Alternate Items 16 & 17)



Retaining Wall Stone Repair
(Bid Alternate Item 18)



Location of Retaining Wall Stone Repair
(Bid Alternate Item 18)

City of Northglenn

Eric Czaikowski
Civil Engineer II

Attachments: Revised Bid Summary dated August 16, 2023

ALL ITEMS IN CONFLICT WITH THIS ADDENDUM ARE HEREBY DELETED.

END OF ADDENDUM NO 1

BID SUMMARY - Revised 8/16/2023

(Contractor Name TBD)

Hereby submits to the City of Northglenn, Colorado the following bid items complete and in place as specified for the:
Croke Reservoir Rail Painting - IFB 2023-019

Item No.	Description	Quantity	Unit	Unit Cost	Total Cost
1	Mobilization	1	LS	\$ -	\$ -
2	Rail Surface Preparation	726	LF	\$ -	\$ -
3	Rail Painting	726	LF	\$ -	\$ -

	Bid Alternate	Quantity	Unit	Unit Cost	Total Cost
4	Pergola Surface Preparation (including 10 columns)	1	LS	\$ -	\$ -
5	Pergola Painting (including 10 columns)	1	LS	\$ -	\$ -
6	Bicycle Station Surface Preparation	1	EA	\$ -	\$ -
7	Bicycle Station Painting	1	EA	\$ -	\$ -
8	Benches Surface Preparation	8	EA	\$ -	\$ -
9	Benches Painting	8	EA	\$ -	\$ -
10	Bollards Surface Preparation	2	EA	\$ -	\$ -
11	Bollards Painting	2	EA	\$ -	\$ -
12	Trash Recepticles Surface Preparation	5	EA	\$ -	\$ -
13	Trash Recepticles Painting	5	EA	\$ -	\$ -
14	Vertical Picket Steel Fence Surface Preparation (height = 43")	305	LF	\$ -	\$ -
15	Vertical Picket Steel Fence Painting (height = 43")	305	LF	\$ -	\$ -
16	Vertical Picket Steel Fence Surface Preparation (height = 70")	835	LF	\$ -	\$ -
17	Vertical Picket Steel Fence Painting (height = 70")	835	LF	\$ -	\$ -
18	Retaining Wall Stone Repair Southwest of Pergola	1	LS	\$ -	\$ -

TOTAL FOR ALL ITEMS \$

TOTAL IN WORDS
